

OTW BARRICADE FENCE PANEL

OVERVIEW & SPECIFICATIONS

- Same-day quotes
- 99% on-time fulfillment
- Lock in pricing for 60 days



OTW SAFETY

otwsafety.com

OTW BARRICADE FENCE PANEL



PRODUCT OVERVIEW

The OTW Barricade Fence Panel may be added to compatible OTW water-filled barricades (OTW 42x72 or OTW 32x72 Rev. D) to help delineate construction work zones, control access to job sites and staging areas, and support site security and privacy. Ideal for perimeters bordering traffic or pedestrian routes. To increase privacy, solid-color or custom screen-printed mesh Privacy Screens may be added.

FEATURES & BENEFITS

- Adds height, security, containment, and optional privacy to a barricade line
- Hot-dip galvanized to ASTM A123 and ASTM A153 for corrosion resistance and long-term outdoor durability
- Integrates with OTW 42x72 and OTW 32x72 Rev. D water-filled barricades
- Stores mounting posts within the frame for efficient shipping and deployment
- Supports OTW Privacy Screens and vehicle or pedestrian gate kits
- One-year manufacturing defect warranty

TECHNICAL SPECIFICATIONS

Panel Dimensions	70.5 × 62.5 in / 179.1 × 158.8 cm
Installed Height (OTW 42x72) (approx.)	8 ft 8 in / 2.64 m
Installed Height (OTW 32x72 Rev. D) (approx.)	7 ft 10 in / 2.39 m
Material	Hot-dip galvanized steel per ASTM A123; hardware per ASTM A153
Tubing	1-3/8 in / 34.9 mm frame and posts, 1-5/8 in / 41.3 mm supports
Privacy Screens	Blue, black, beige, green; single, 5- and 8-panel lengths; custom screen-printing available



Note: Ballast barricades with water before installing fence panels.

OUR PROCUREMENT PROMISE

- **60-Day Price Lock:** We lock in your product and freight pricing for a full 60 days—we absorb the risk so you can plan with 100% certainty.
- **Fast Quote Guarantee:** Time is money on the job site. Submit your request by 4:00 PM MT, and we will have a formal quote in your inbox the same business day.
- **Real-Time Stock Verification:** Inventory moves fast. Call us at 888-363-7740 for an immediate, real-time stock check to ensure your project stays on schedule.